

**City of Florence
600 w 3rd street
Florence, Colorado
81226**

BID FORM

BID SCHEDULE D – Addendum #5– Sunnyside Street

ITEM NO.	ITEM DESCRIPTION	QTY.	UNIT	UNIT COST	UNIT TOTAL
1	Mobilization/ Demo	1	LS		
2	Traffic Control		LS		
3	Surface prep	3,600 SQFT	SQFT		
4	Curb and gutter	1,200 LF	LF		
5	Sidewalk	7,295 SQFT	SQFT		
6	3" Mill	14,400 Sq FT	SQFT		
7	Concrete pan 45'X5'	225 SQ FT	SQFT		
8	3" paving	18,005 SQ FT	SQFT		
9	surveyor		LS		
10	Patch back	98Ton	Ton		
11	Concrete Pan 6'x30ft Alta	180Sqft	SQFT		
12	5 ADA Ramps type C	150SQFT	SQFT		

BID SCHEDULE D TOTAL PRICE

(Use Words)

(Use Figures)

Scope of Work

1. Prep subgrade for hot bituminous- 2' on east side of roadway and 4' on the west side of the roadway, will need to be excavated and graded to correct drainage issues and to provide a suitable base capable of supporting a minimum of 3" hot bituminous to ensure structural integrity. 3,600 Sq Ft
2. Remove and replace 90 LF of existing curb on the west side of roadway
3. Place 690 linear feet of 6-inch curb head on west side of road
4. Place 10' of mountable curb on southeast side of roadway to adjoin with shell driveway then continue with 600 LF of 6" curb head
5. Install a 3-inch-thick compacted layer of hot bituminous asphalt over the specified square-foot area. Glass fibers are to be incorporated into the asphalt mix. This work includes the area where approximately 90 linear feet (LF) of curb has been removed and replaced.
6. Cold plane 3" in depth of existing roadway for uniform repair.
7. Place a 3" inch compacted mat of hot bituminous for sq ft.
8. All water valves and utility covers must be raised or lowered to meet new street surface.
9. Driveway cuts 16, 2 of them being alley entrance
10. One (1) cross pan on E 2nd St. - 45' long x 5' wide (25 sq yd)
11. Six (6) ADA ramps in total: two (2) ramps at the intersection of E. 2nd Street and Sunnyside; one (1) ramp at each corner of E. 3rd Street and Sunnyside; and two (2) ramps at the Alta driveway, one (1) on each side.
12. One (1) curb pan 2 feet wide x 30 feet long at Alta driveway.
13. Saw cut Alta driveway for seamless integration of new pan and road

Notes:

1. Project to be completed by 12/31/2026