

**City of Florence
600 w 3rd street
Florence, Colorado
81226**

BID FORM

BID SCHEDULE C – Addendum #4 - Sunnyside Street

ITEM NO.	ITEM DESCRIPTION	QTY.	UNIT	UNIT COST	UNIT TOTAL
1	Mobilization/ Demo	1	LS		
2	Traffic Control		LS		
3	Surface prep	4,800	SQFT		
4	3" Mill	14,400	SQFT		
5	3" paving	19,200	SQFT		
6	surveyor		LS		
7	Patch back	98Ton	Ton		

BID SCHEDULE C TOTAL PRICE

(Use Words)

(Use Figures)

Scope of Work

1. Prep subgrade for hot bituminous- 4' Four feet on each side of roadway starting at existing curb will need to be excavated and graded to correct drainage issues and to provide a suitable base capable of supporting a minimum of 3" hot bituminous to ensure structural integrity.
2. Cold plane 3" in depth of existing roadway for uniform repair.
3. Place a 3" inch compacted mat of hot bituminous for 19,200 sq ft.
4. All water valve, and utility covers must be raised or lowered to meet new street surface.

Notes:

1. Project must be completed by 12/31/2026
